



Precision Crawlspace & Restoration

Courtney Powers
104 Pine Forest Drive
Henderson, NC 27537

(252) 902-7827
 admin@turnerhometeam.com

INVOICE	#25
SERVICE DATE	Jul 27, 2026
PAYMENT TERMS	Upon receipt
DUE DATE	Jul 28, 2026
AMOUNT DUE	\$0.00

CONTACT US

1210 Strickland Rd
Walstonburg, NC 27888

(252) 717-0789
 steveford.pcr@gmail.com

INVOICE

Services	qty	unit price	amount
Sealed Crawlspace (12Mil Moisture Barrier) Install 12 Mil reinforced moisture barrier throughout crawlspace to create a sealed environment. Work includes full ground coverage with moisture barrier, sealing all seams and, and mechanically fastening barrier to foundation walls and around piers. All penetrations will be properly sealed to prevent moisture intrusion. System is designed to reduce humidity, improve air quality, and protect structural components from moisture-related damage.	1.0	\$1,850.00	\$1,850.00
Sump Pump Installation with Exterior Discharge & Pop-Up Drain Install sump pump system to collect and remove groundwater. Work includes setting sump basin, installing sump pump, and connecting discharge piping. Discharge line will be routed to the exterior of the home and extended away from the foundation, terminating at a pop-up drain emitter to allow controlled water release. System will be installed to ensure proper drainage, functionality, and long-term protection against moisture intrusion.	1.0	\$1,200.00	\$1,200.00
Dryer Vent Duct Replacement Provide labor and materials to remove the existing dryer vent duct and install new code-compliant rigid metal dryer ducting. Scope includes securing all connections, minimizing airflow restrictions, properly venting to the exterior of the home, and testing for proper airflow to improve dryer performance and reduce fire hazards.	1.0	\$400.00	\$400.00

Subtotal	\$3,450.00
Job Total	\$3,450.00
Amount Due	\$0.00

Payment History			
Jul 29	Wed 10:46am	Credit Card	\$3,450.00

See our [Terms & Conditions](#)

